

**THE SINCLAIR/TIMEX USERS MAGAZINE**


**\$250**

**Volume IV**

**MARCH 1986**

**Number 3**

## *Connecting a Plotter to the TS-2068*



*Also in This Issue:*

**Interfacing Printers to the Sinclair QL  
Creating Additional Colors on the TS-2068  
Type-In Game for the TS-1000**



**WOW!**

**AT LAST!! A VERY AFFORDABLE COMPUTER  
AT A VERY AFFORDABLE PRICE**

POWERFUL FULLY PROGRAMMABLE WITH 2K OF MEMORY—PORTABLE—678 × 138 INCH MODULE SINGLE-KEY ENTRY COMMANDS—DURABLE 40 KEY MEMBRANE TYPE KEYBOARD—280A BASED FOUR CHIP DESIGN—EDUCATIONAL—UNIQUE SYNTAX-CHECK REPORT CODES FOR ERROR IDENTITY—GRAPH DRAWING AND ANIMATED DISPLAY—ACCURATE TO 9-1/2 DECIMAL PLACES FOR FULL RANGE MATH AND SCIENTIFIC FUNCTIONS—AT AN AFFORDABLE PRICE

WE CANNOT TELL YOU THE MAKE OF THE COMPUTER BUT IT WAS MADE BY A FAMOUS WATCH COMPANY. THEY USED TO SELL FOR \$99.95

WE BOUGHT OUT WHAT THE FACTORY HAD LEFT IN STOCK AND HAD TO REMOVE THE LABELS. THESE UNITS ARE UNPACKAGED. LESS THE 9V WALL ADAPTER AND MANUAL BECAUSE THIS IS A DISCONTINUED ITEM THERE IS NO WARRANTY.

GET THEM WHILE THEY LAST

LIMITED SUPPLY

BUY 1st UNIT FOR \$19.95    BUY 2nd FOR \$16.95    9V DC WALL ADAPTOR    \$4.95

BUY THE 3rd UNIT (NON OPERATING FOR PARTS) \$10.95    MANUAL (OVER 150 PAGES)    \$2.95

See September 1984 issue of 73 for TIMEX/RTTY article

**CHIP BONANZA (AT THESE PRICES THEY ARE A STEAL)**

2708	.....	\$1.00 EA OR 10 FOR \$ 9.00
2716	.....	\$2.25 EA OR 10 FOR \$20.00
2732	.....	\$3.25 EA OR 10 FOR \$30.00
2784	.....	\$4.00 EA OR 10 FOR \$35.00
27138	.....	\$7.00 EA OR 10 FOR \$60.00
6502	.....	\$4.95 EA OR 10 FOR \$45.00
6810	(REG \$3.95)	\$1.95 EA OR 10 FOR \$18.00
68A00	(REG \$19.95)	\$5.95 EA OR 10 FOR \$50.00
68A21	(REG \$9.95)	\$2.95 EA OR 10 FOR \$25.00
4118	(for equivalent)	8 FOR \$ 5.95
4134	.....	9 FOR \$12.95
XR-2211	(SPECIAL)	\$ 2.95
TMS 9800NL MICRO-P 64 PIN 8 BIT DIB + 16 BIT CPU	.....	\$ 4.95
TMS 9801NL MICRO-P PSI	.....	\$ 2.95
TMS 9901NL MICRO-P CLOCK GEN. AND DRIVER	.....	\$ 5.95
TMS 9918ANL MICRO-P COLOR GRAPHICS AND DISPLAY	.....	\$ 9.95
KEYBOARD (99/4) 48 KEYS MEASURE 4 × 10 (H-TEK)	.....	\$ 9.95

**HAL'S COMPUTER GOODIES**

Timex printer ..... (reg. \$99.95) now \$59.95

Coleco cassette player (battery op.) ..... \$29.95

9V. @ 600 Ma. adapter (needed for 18K RAM packs) ..... \$7.95

18K RAM pack module, new ..... \$29.95

18K RAM pack module, refurbished ..... \$19.95

RCA TV interface cable ..... \$1.25

Dual jack cassette interface ..... \$2.50

TV/Computer game switch ..... \$3.95

**Cassette Software:**

I have cassette software send for list (reg. \$9.95-\$14.95)

Hal's Special Price: 1 for \$3.95; 3 for \$10.95; 8 for \$19.50

10 for \$29.50; 20 for \$50.00

or let Hal select 25 different cassettes (my choice) at 25 for \$50.00!!!

APPLE II and APPLE II+ COMPUTER MAINFRAMES fully populated \$150

Power supply, case and keyboard, separately available Call or Write

Unit as described above, fully assembled & tested \$350 plus shipping

APPLE POWER SUPPLIES ..... \$29.95

SHIPPING INFORMATION: ORDERS OVER \$25 WILL BE SHIPPED POST-PAID EXCEPT ON ITEMS WHERE ADDITIONAL CHARGES ARE REQUESTED ON ORDERS LESS THAN \$25. PLEASE INCLUDE ADDITIONAL \$2.50 FOR HANDLING AND MAILING CHARGES. MICHIGAN RESIDENTS ADD 4% SALES TAX. SEND 20¢ STAMP OR BARE FOR FREE FLYER. CANADIAN ORDERS ADD \$5.00 POSTAGE IN U.S. FUNDS.

**HAL-TRONIX, INC.**  
P.O. BOX 1101 - DEPT. HR  
SOUTHGATE, MICH. 48195  
PHONE (313) 285-1782

"HAL" HAROLD C. NOWLAND W8ZXH

**FOOTE**

**SOFTWARE**

*TS2068 ROM Software*

Badgammon .....	\$15.00
U.S.A. (Presidents/States & Capitols) .....	\$12.95
Calorie Counter .....	\$12.95
Advanced Math (Calculus) .....	\$12.95

*Add \$1.00 on all orders for shipping/handling*

**FOOTE SOFTWARE**  
P. O. Box 14655 — Gainesville, FL 32604-4655  
904/462-1086 6-9 p.m. EST

**S**

TS 1000

**U**

TS 1500

**M**

TS 2068

**THE SINCLAIR/TIMEX USERS MAGAZINE**  
3224 Northwest 30th Avenue  
Gainesville, Florida 32605  
904/378-9000 or 462-1086 evenings

EDITOR ..... Joe Williamson  
PUBLISHER ..... Richard Cravy  
STAFF WRITERS ..... Bill Woodward & John Monkus

**SUBSCRIPTION RATES 9/1/85**

Regular Subscription (U.S.) .....	\$15.00/year
Canadian Subscription .....	\$18.00/year

All other countries please inquire first  
Published monthly

**ADVERTISING RATES 9/1/85**

Full Page .....	\$75
Half Page .....	\$45
Quarter Page .....	\$25
Eighth Page .....	\$15

These prices do not include artwork or ad layout. There will be an extra charge for custom ad work. Ads should be in our offices by the 10th of month of publication.

**Classifieds:** \$2.00 per line. FREE personal ads for subscribers (no dealers).

**SUBMISSIONS**

We are willing to pay for articles published (after editing). Our current rate is 10¢ per text line and 10¢ per program line (after editing). Authors should indicate if they wish to be paid when submitting material.

**CORRESPONDENCE**

Please provide us with all information on your mailing label in all correspondence. Your subscription expiration is printed on your label with four digits; the first two indicate the year, the last two the month. Please tell our advertisers you saw their ad in SUM.

**Smart Text TS-2068**

**and the new**

**Smart Text OS-64**  
(For the Zebra OS-64 Cartridge)

With Universal Intfc/Printer Patch  
For all Configurations

Three Integrated softwares that does most all administrative functions  
Word proc - Data files mgt - Mailing List - Form Letters - Mailing Labels  
Repeat printing - Auto Letter Heads.


Supports all Printers, plus TS-2040.

29.95 + \$3.00 mailing to: Bill Jones  
Gulf Micro, 1317 Stratford Ave,  
Panama City, FL 32404



# Another Dimension in 2068 Computing...

## Using a Plotter



The versatile TS 2068 computer never ceases to amaze me on its capabilities. Each of us has a pet application for their computer; mine is information and productivity. Here, I define productivity as the use of skills and resources to maximize output of a deliverable item. In a nutshell, my computing must do something, and preferably make something!

After adding a dual 3 inch disk drive unit by Amdek via a Zebra controller to my 2068, something new was lurking in my brain: plotting! I've been interested in plotting for many years, having cut my teeth on plotting Grand Daddys by Calcomp and Hewlett-Packard. In fact, in my manual on Smart Term II Telecommunications, the cover, notes, and hex/ASCII tables were each designed and printed on a "borrowed" HP 9845B computer and HP flatbed plotter.

If you are still wondering what a plotter can be used for, here is a small list of applications to stir your imagination:

1. Art, Illustration, and Graphics design
2. Bulletins, Greeting cards, Letter heads
3. Low cost Computer aided design (CAD)
4. Optical Photo digitizing
5. Publication quality graphics and Text Formatting

For optical photo digitizing, you could replace the pen with an opto-electronic sensor and feed the information into the joystick port, saved in memory to be printed on the screen or printer later.


Plotter prices have generally stayed at a high level because their application

attracts the more sophisticated business or engineering user. Currently, prices have bottomed out at about \$200 and can go up to "skys the limit" prices for sophisticated CAD/CAM equipment.

My plotter is a flatbed model DXY-100 by Amdek. This plotter is currently being offered at a close-out price for \$125 from Peripherals Direct; originally listing for \$599! Initially, the concern was whether the DXY-100 would interface to the 2068. So I wrote to Amdek Corporation requesting a copy of the owner's manual so I could review the plotter's operation, instructions, and interfacing. My concern was eased when it was learned that the DXY-100 would connect to any Centronics interface. Also, the command set was easy to learn and program; as each command is activated by the LPRINT keyword.

The DXY-100 plotter has excellent solid construction (Akin to their 3 inch disc drive), with overall dimensions of 25(W)x4(H)x17(D) inches. It comes in two sections, consisting of the flatbed and electronics controller unit. The bed contains the mechanics consisting of two stepper motors and guide wires to move the arm and pen in an X & Y direction. The up/down motion of the pen is controlled by a solenoid.

The controller portion contains the power supply, central processor, ROM software, and two open ROM slots. These slots can be filled with 2716 EPROMs to provide custom programs, character sets,





etc. An optional ROM is also available which provides six additional commands to draw circles, arcs, and perform cross-hatching. These commands are useful for pie and bar chart plotting for business type graphics. Three pens and holders are supplied, but you can use most any felt tip or ball markers which will fit into the holder opening. Three magnetic strips are supplied as paper hold downs. The bed will take paper or transparencies up to 14 x 18 inches. It comes standard with parallel interface and command syntax in firmware, including a self-test mode. The following listing provides the command set:

## List of Drawing Commands for the DXY-100

COMMAND	INPUT FORMAT	FUNCTION
D (DRAW)	D x1,y1,x2,y2 .....xn,yn	Draws lines from the present pen position to (x1,y1), from (x1,y1) to (x2,y2)..... from (xn-1, yn-1) to (xn,yn) respectively. X must be an integer value <= 3600. Y must be an integer value <= 2600. The X and Y values are multiplied by .1 mm to get actual distance. The values must be absolute coordinates. Draw moves the carriage with the pen down.
M (MOVE)	M x,y	The same as "D" above except that the pen is up.
I (Relative)	I x1,y1,x2,y2 .....xn,yn	Draws lines from the present position to the relative coordinates (x1,y1), from the new position to the relative coordinates (x2,y2)..... Coordinates are relative to the previous point. Ranges for X and Y are the same as D above. The carriage moves with the pen down.
R (Relative)	R x,y	Same as function I above except that the pen is up.
L (Line type)	L p	If p=0 then solid lines are drawn. If p=1 then dotted lines are drawn. Once assigned line type does not change until reassigned. The LINE SCALE command can come either before or after this command. Default is p=0.
B (Line scale)	B l	Assigns the ratio of line to space for dotted lines. l <=255. Default is l = 30.
X (Axis)	X p, q, r	Draws an axis of coordinates which is parallel to the y axis if p=0, or the x axis if p=1. q is the distance between the scale marks. r is the number of scale marks drawn.
H (Home)	H	Move the pen back to the home position with the pen up. If an error occurs, the error LED is turned off.
S (Alpha Scale)	S n	Assigns the size of characters and marks. 0 <= n <= 15. Character size is .7(n+1)mm by .4(n+1)mm. Character spacing is .3(n+1)mm. Default is n=3.

Q (Alpha Rotate)	Q n	Sets the angle at which characters are drawn. n is 0, 1, 2, or 3 and rotate the characters drawn 0, 90, 180, or 270 degrees respectively. Default is n=0.
P (Print)	P c1, c2,...cn	Draws characters c1, c2,...cn.
N (Mark)	N n	Draws a scale mark at the current position of the pen. n is the length of the mark.
U (User)	U n	Allows the user to assign an optional set of characters. n=1 to 4. EXTROM 1 has U1 and U2. EXTROM 2 has U3 and U4. Without the expansion roms installed, this command causes an error.
(ESC) (Exchange)	(ESC) n CHR\$(27)+"n"	Changes the mode. n is a number 0 to 2. n=0 is plot mode. n=1 is printer mode. n=2 is self test mode. Default n=0.

### PROGRAM #1

```

100 REM *** M,D COMMAND ****
110 A=300: REM SIZE
120 FOR X=1500 TO 0 STEP -50
130 FOR Y=1700 TO 200 STEP -50
140 IF Y <> X THEN 200
150 LPRINT "M";X;",";Y
160 LPRINT "D";X+A;",";Y
170 LPRINT "D";X+A;",";Y+A
180 LPRINT "D";X;",";Y+A
190 LPRINT "D";X;",";Y
200 NEXT Y
210 NEXT X
220 LPRINT "H"
230 END

```

### PROGRAM #2

```

100 REM *** SWIRLING ***
110 PI=3.1416
120 X=1300:Y=900
125 D=0
130 LPRINT "M";X;",";Y+D
140 FOR N=0 TO 30
150 FOR I=0 TO 2*PI STEP PI/100
160 D=D+.1
170 A=INT(D*SIN(I)+X)
180 B=INT(D*COS(I)+Y)
190 LPRINT "D";A;",";B
200 NEXT I
210 NEXT N
220 LPRINT "H"
230 END

```

With a plotter, artistic aficionados can explore new horizons in computer art. Besides mathematical of random based plotter art, interactive plotter art programs become possible. You can write programs to allow movements of a joystick or cursor keys to control the plotter's pen movements.

Barry Carter  
Detroit, MI



# Targets Five

## A Game for the TS-1000

TARGETS FIVE is a program that will require a RAM Pack on your TS-1000. It is a slow-acting routine of an arcade type of game, but you can have a lot of fun with it. You get four shots to shoot down five targets. It can be done.

Nested loops such as 510-580 are time consuming. But the action can be speeded up by adding a line like:

```
515 IF CODE A$(L)= 0 THEN NEXT L
```

This will eliminate unnecessary scanning. Otherwise, it is a "bare bones" routine that you may embellish yourself.

There will be a TS-2068 version in an up-coming issue of QuarTerS Magazine in my "Basic Tutor" column.

```
4 FAST
5 PRINT TAB 8;"RULES OF GAME"
;TAB 7;"-----"
10 PRINT ,,"-GAME STARTS WITH
5 TARGETS"
15 PRINT "-PLAYER MAY USE UP T
0 4 SHOTS"
20 PRINT "-SHOT LAUNCHER SWEEP
S OVER"," FIRING RANGE 2 1/2 T
IMES"
25 PRINT "-OBJECT: TO WIPE O
UT TARGETS"
30 PRINT "-FIRIE USING THE M (M
ISSILE) KEY"
35 PRINT ,,TAB 11;"GOOD LUCK"
40 PRINT AT 20,3;"PRESS ENTER
KEY TO START"
45 INPUT Z$
50 CLS
92 LET W=0
94 LET S=0
96 LET B=13
98 LET K=1
100 LET AA=PEEK 16396+256*PEEK
16397
105 RAND
110 DIM A$(5,3)
120 FOR N=1 TO 5
130 LET A$(N)=" "
140 NEXT N
190 CLS
195 FAST
200 FOR L=1 TO 5
210 PRINT AT L, INT (23*RND)+3;A
$(L)
220 NEXT L
230 SLOW
240 FOR T=1 TO 20
```

```
250 NEXT T
300 LET S=S+1
310 IF S>70 THEN GOTO 600
320 LET B=B+K
330 IF B<2 OR B>26 THEN LET K=-
K
340 PRINT AT 20,B;" [ ] ";TAB B-
1;" "
350 LET C$=INKEY$
355 IF C$="M" AND RND>.2 THEN G
OTO 400
360 GOTO 300
400 LET W=W+1
420 FOR M=18 TO 0 STEP -1
430 PRINT AT M, B+1;" [ ] ";TAB B+1;
" "
440 NEXT M
445 PRINT AT 0, 0;"SHOTS= ";W
450 FOR T=1 TO 40
460 NEXT T
500 FAST
510 FOR L=5 TO 1 STEP -1
520 LET H=0
530 FOR C=3 TO 28
540 IF PEEK (AA+33*L+C+1)=131 T
HEN LET H=H+1
550 IF H=3 THEN GOTO 580
560 NEXT C
570 IF H<3 THEN GOSUB 610*L
580 NEXT L
590 LET X=CODE A$(1)+CODE A$(2)
+CODE A$(3)+CODE A$(4)+CODE A$(5)
)
591 IF X=0 THEN GOTO 595
592 IF W=4 THEN GOTO 600
593 CLS
594 GOTO 190
595 CLS
596 PRINT AT 8, 6;"YOU HIT ALL T
ARGETS"
598 GOTO 604
600 CLS
601 IF S>65 THEN PRINT "LAUNCHE
R RAN OUT OF FUEL"
602 IF W=4 THEN PRINT "YOU HAD
YOUR 4 SHOTS"
603 PRINT AT 8, 6;"YOU DID NOT M
AKE IT"
604 PRINT ,,TAB 3;"TO PLAY AGAI
N PRESS Z KEY"
605 SLOW
606 IF INKEY$="Z" THEN GOTO 50
607 GOTO 606
610 LET A$(1)=" "
620 RETURN
1220 LET A$(2)=" "
1230 RETURN
1830 LET A$(3)=" "
1840 RETURN
2440 LET A$(4)=" "
2450 RETURN
3050 LET A$(5)=" "
3060 RETURN
```

WARREN FRICKE  
273 CANTON STREET  
DEPEW, NEW YORK 14043



# Using Parallel Interface Printers With the QL

Technology Research and other QL hardware manufacturers have introduced centronics parallel interfaces to allow the QL to drive parallel printers, which are more common than serial interfaced printers.

Some information on how to install these parallel interfaces to work with the QL's software is given in the INFORMATION section of the QL manual. Additional information may also be supplied by the interface manufacturer. To clarify and amplify some of that information, the following has been compiled.

To use the parallel interface in BASIC programs, call for it exactly as you would the SER1 and SER2 serial interfaces. That is, specify a channel to open, followed by the peripheral designation PAR. Examples:

```
10 OPEN #3, ser1      (opens channel 3 to
                      serial port 1)
```

```
0 OPEN #5, par        (opens channel 5 to
                      parallel port)
```

To install the parallel interface to work with Quill, Archive, Easel, or Abacus, turn on or reset the computer without any cartridges in either microdrive. Select F1 or F2 for monitor or TV. Then...

1. Put backup copy of Quill in mdv1 (or flp1 for disk). Load and run INSTALL BAS. (If using a disk system, first specify that the disk system is to act like microdrives. This is done with FLP USE MDV on the Technology Research unit. Then load and run the install program.)
2. Specify where the new printer installation data is to be saved by the program when it prompts for it.
3. Press the SPACE BAR to indicate a parallel interface will be installed.
4. Select the appropriate printer from the menu provided.
5. Select EDIT by pressing F2 then use the cursor keys to change PORT: NONE to read PORT: PAR.

6. ESC to end editing then F5 to save the new installation information on your microdrive or disk.

7. Exit the install program and RESET the computer before trying to use any other program.

If everything has been done right, any print call from within Quill or the other software will now direct output to the parallel interface. A separate microdrive cartridge set up for serial interfaces should be kept for using serial printers.

A FINAL NOTE: There is another alternative. There are serial to parallel cables available for about \$45-50 from English Micro Connection which allows the user to plug one end in SER2 and the other end into a parallel printer. No other installation procedures are necessary since the computer still thinks it is dealing with a serial interface and printer.

-- Richard Cravy

---

The January issue of SUM contained a program for solving Jumbled Word Puzzles. Robert Fischer went to work and developed a much shorter version of the BASIC program which will also allow words of any length up to 16 characters (but only 6 fit in the on-screen box). To start over, push the zero key. To communicate with Mr. Fischer, write to 221 Scoggins Street, Summerville, GA 30747.

```
10 POKE 23658,8: BORDER 0: PAP
ER 0: INK 7: CLS: PRINT AT 2,9:
INK 2:"S H U F F L E": INK 7: P
LOT 72,103:: DRAW 104,0: DRAW 0,
-25: DRAW -104,0: DRAW 0,25: PRI
NT AT 20,6: INK 1:"ENTER 2 TO 6
LETTERS": INPUT B$: LET A=LEN B$
110 PRINT AT 20,3:"PRESS ANY KE
Y TO CONTINUE ",TAB 10:"0 RESTAR
TS": LET Z#=B$: LET C#="": FOR I
=1 TO A
140 LET R=INT (A*RND)+1: IF B$(
R)="" THEN GO TO 140
160 LET C#=C#+B$(R)+" ": LET B$(
R)="" : NEXT I: PRINT AT 10,16-
A: INK 6:C#
220 LET B#=Z$: PAUSE 0: LET A#=
INKEY$: GO TO 110-(100 AND A#=""
)
450 SAVE "SHUFFLE" LINE 10
```



# Creating Additional Colors on the 2068

If you have ever felt limited on the 2068 with only eight colors, here is a way to create up to fifteen NEW colors and twelve new shades of the ones you already have. Whats the catch? Well, actually there are two. One, you are limited to the new color being the size of the 8 x 8 character grid. Two you have to be using an RGB monitor.

We are not actually creating a new color, we are only making our eyes think they are seeing new color. The first thing we must do is to re-create the graphic character they forgot to bring up from the TS 1000. Remember the gray (first clue) "hash" mark they had? In the 8 x 8 grid, the pixels alternated white and black. With their close proximity, the character as a whole appeared to be gray. With this character on the 2068, if we make the INK yellow and the PAPER red, we get orange.

We need an RGB monitor to see this because of its increased resolution over composite monitors. You can try this on a composite monitor, but most likely you will only get squiggly color lines over this character.

To generate the character, you need to define a graphic character as shown in chapter 18 in the 2068 manual. Use BIN 10101010 = 170 decimal and BIN 01010101 = 85 decimal alternately. Enter the program as shown using the GRAPHICS A where you see the "hash" mark. You can try only making this half of a character to create higher res. graphics of your own.

The new colors can really brighten up your displays and give a new dimension of color possibilities on the 2068. For those who built the RGB interface shown last month now have the opportunity to really see the difference between their old composite screen and an RGB one!

Joe Williamson

```
10 FOR n=0 TO 7: READ a: POKE
USR "a"+n,a: NEXT n
20 DATA 170,85,170,85,170,85,1
70,85
30 FOR n=1 TO 10
40 PRINT PAPER 1; INK 1;"██"; I
NK 2;"██"; INK 3;"██"; INK 4;"██"
50 PRINT PAPER 2; INK 2;"██"; I
NK 3;"██"; INK 4;"██"; INK 5;"██"
60 PRINT PAPER 3; INK 3;"██"; INK 4;"██"; INK 5;"██"
70 PRINT PAPER 4; INK 4;"██"; INK 5;"██"; INK 6;"██"
```

```
80 PRINT PAPER 4; INK 4;"██"; INK 5;"██"; INK 6;"██"
90 PRINT PAPER 5; INK 5;"██"; INK 6;"██"; INK 7;"██"
100 PRINT PAPER 6; INK 6;"██"; INK 7;"██"; INK 8;"██"
110 NEXT n
120 PRINT ""
130 FOR n=1 TO 10
140 FOR m=1 TO 8
150 PRINT PAPER 0; INK m;"██"; P
APER m;"██"; PAPER 7;"██"; " "
160 NEXT m
170 PRINT ""
180 NEXT n
```

---

## Celestial Basic

(Eris Burgess's CELESTIAL BASIC is a collection of astronomy programs originally written for the Exidy Sorcerer computer. These programs were rewritten for the Apple II and published under the above title in 1982 by Sybex. In 1983 another rewrite adapted some of the more important programs to Timex Sinclair BASIC. The result was MORE USES FOR YOUR TIMEX/SINCLAIR 1000: ASTRONOMY ON YOUR COMPUTER, 20 programs which run on the TS 1000, ZX 81, and Spectrum computers.)

PLANET FINDER plots the positions of the sun, moon, and planets for any date, time, and location. The solar system objects are shown within an area of the sky approximately 30 degrees wide by 30 degrees high - a size appropriate to the display of one zodiacal constellation at a time. The "window" on your monitor screen is nearly identical to the field of view of a 35mm camera.

The user first enters local longitude. Then the time for the display is requested: year, month, and date. Local time information is not necessary. The display is based more on the actual configurations of the celestial bodies than on the circumstances of observation.

The conventions used to identify the object to be viewed are as follows: Venus through Pluto are identified by their initial letters. The sun is an "O", and Mercury is a "+" sign to avoid confusing it with Mars. The moon is shown as a ")" regardless of its phase.

The first display shown is a brief table of data recalling the display date, the object chosen, and its right ascension and declination (the astronomer's longitude and latitude). An opportunity is given to COPY the screen information before continuing with the sky display.

The graphic display which follows repeats the date and object information along with the name of the zodiacal constellation in which the desired object is found on that date. Below this information is the view of the sky. The graphic depiction of the constellation is good enough that experienced observers would have no trouble recognizing it even if it were not identified. The object is displayed in its proper position within

the constellation, along with any other planets which happen to be in the same area of the sky. Once again the option to COPY the screen is given. The user is asked whether the display of another planer or date is desired.

The program can be typed in from the Sybex book, or a tape (\$12.00) is available to eliminate hours of typing, proofreading, and editing. Contact Sybex Inc., 2344 Sixth Street, Berkeley, CA 94710 for the book. For the tape and an occasional "Celestial BASIC User's Newsletter," write directly to author/developer Eric Burgess at S & T Software Service, 13361 Frati Lane, Sebastopol, CA 95472.

Duncan R. Teague

---

## A Beginner on the QL

I took the Quantum Leap! I liked the computer so much I bought the company! No, I didn't have the sixteen million dollars.

All kidding aside, I liked the QL so much I took it and my printer to my daughter's to help her finish a term paper. After we had the paper ready to turn in the next day, I decided to leave my QL and printer with her until I could get her a set.

We were using the QL, Spirit 80 printer and a Sears 12" B&W Monitor/TV with a monochrome monitor cable, plugged into a three outlet surge protector w/switch. The whole rig can be switched off or on at one time.

Loading was simple. Switch on. Insert microdrive program cartridge in drive 1 and a file or formatted cartridge in drive 2. To boot, press F1 or F2 and watch program load in about 10 seconds. If you do not remember the name of your document, press F3 (command), "1" (LOAD), and "?" (directory). The directory with number of unused sectors is displayed in the upper left corner. Type in File name and ENTER. File is loaded in a few seconds. NO CASSETTE RECORDER or TAPES to worry with. NO "TAPE LOADING ERROR".

Before we finished, she said, "Daddy, Quill has made me hate Tasword and the 2068!" The next day, I took out a loan and sent for her a QL and printer. Bob Dyl of English Micro Connection had my QL delivered on the 18th of December.

I am editor of the Stroke Club bulletin and needed a user friendly filing system that would keep all club records and print mailing labels. I used to print my labels on the TS-2068 with a brute force BASIC program. That is because I could never make heads or tails of Masterfile.

When I ordered the QL from EMC, I told Bob Dyl that I needed to drive a parallel printer. He sent the QL with a Kempston Centronics interface. I had to have my RGB cable made locally.

The print driver, for most printers, is on the program cartridge and very simple to modify for the Spirit 80 printer. My printer was up and running in no time.

Since most of my time has been spent using Quill, my reactions to the QL are flavored by it. If you are wanting to write letters and memos of 1000 words or less (about 5 double spaced pages) the basic QL and Quill is fine; otherwise the QL needs more on-board memory.

I have a mental handicap caused by two strokes. I have to have a word processor in order to write. The QL and Quill have made my life infinitely easier than the TS 2068 and Tasword or Wafadrive and SpectralWriter.

My early problems with the QL stemmed from mental handicaps. Richard Cravy and others have steered me in the right direction and I have forgotten some of the early obstacles I had to overcome.

I find the QL Users Guide with its 400



pages very easy to understand and follow. I think a beginner will find SUPERBASIC easier than BASIC to program in. I find it that way. I have entered all the stroke club names and addresses into MAIL LIST and will try to print the mail labels from it for next month's mailing. At the present my printer is 50 miles away at my daughter's.

The biggest factor in my buying the QL was economic. When I priced what it would cost me to upgrade my 2068 to what was standard equipment on the QL, I could pay for the QL and have a 32 bit computer to boot. The straw that broke the camel's back was seeing the QL in RGB (80 column) on a SEAR's Total Video System. There were no squiggles. The Sear's B&W monitor is just as sharp in monochrome.

My daughter is in her senior year, last semester at the University of Florida. She is a beginner at computers but took to the QL like a "duck to water" after that day when I helped her get her class paper prepared to turn in. I typed (two finger) while she wrote. When she finished the writing she (a touch typist) finished typing the last 6 of 17 double-spaced pages. The two most important things I taught her was how to hyphenate and how to call the HELP FILE.

My advice, unless you are a game addict, is to buy a QL when you are ready to move up from your present computer.

-- Bill Woodward

ADDITIONAL NOTE: I had 40 cartridges to FORMAT. In BASIC type in AUTO and get automatic line numbering starting at 100. You can then use this program to format them with:

```


100 paper 255
110 for x=1 to 10
120 format mdv1_
130 next x
140 cls
150 paper 7,2
160 for x=1 to 10
170 format mdv2_
180 next x
190 cls
200 goto 100

```

Insert a blank cartridge in both mdv1\_ and mdv2\_. The light will shift from 1 to 2 and the screen will change color about every five minutes. You can even have the

QL sound off as it changes from mdv1 to mdv2 and return.

-- Bill Woodward



## FREE SPECTRUM SOFTWARE!



That's right! While supplies last, you will receive **THREE** assorted SPECTRUM Software Cassettes — **FREE!** when you purchase the RAINBOW *plus* SPECTRUM Interface!

The RAINBOW *plus* is a complete Spectrum Interface offering Spectrum emulation PLUS a Spectrum hardware compatible expansion port with ALL-IN-ONE compact plastic case ... and for only **\$49.95!**

And the savings don't stop there ... We are also offering the Rotronics WAFADrive\* for only **\$99.95** with the purchase of the RAINBOW *plus*; or a combo price of **only \$149.90** and still get the **FREE** Software.

The WAFADrive offers ● two 128K high speed drives ● Fast reliable access ● SPECTRUM compatible ● RS232 (serial) port ● parallel (Centronics) port ● extended Basic O.S. ● Blank wafer ● A very powerful word processor.

\*Since the WAFADrive is a SPECTRUM device, the RAINBOW *plus* is required for operation with the TIMEX 2068.

### TO ORDER:

Send Check, Money Order

VISA or MASTERCARD to:

**DAMCO ENTERPRISES**

**67 Bradley Ct.**

**Fall River, MA 02720**

or call **(617) 678-2110**



# English Micro Connection

---

**"Bridging the Atlantic to Bring You the Best in English Hardware and Software"**

---

## First Anniversary Customer Appreciation Sale We are having a birthday and you get the gifts!

We are a year old thanks to our customers and friends who have made **English Micro Connection** successful. We have decided to give you the birthday gift. We are taking our strongest sellers and offering them to you at unheard of prices.

Gremlins — was 13.95 now 7.95  
Brian Bloodeaxe — was 12.95 now 7.95  
Glass — was 11.95 now 6.95  
Go To Hell — was 10.50 now 8.50  
Starion — was 11.95 now 5.95  
Softaid — was 6.95 now 5.95  
Spy Hunter — was 12.95 now 7.95  
Super Pipeline II — was 11.95 now 6.95  
Backpacker's Guide to the Universe — was 12.95 now 7.95  
Cauldron — was 12.95 now 7.95  
Archon — was 12.95 now 7.95

**BONUS!** The latest smash hit from England  
**Rambo** — was 13.95 now 10.00

### ***Special!!***

HiSoft's C Compiler for the Spectrum,  
was 34.50 now 21.95

### **HARDWARE SPECIAL!**

Mura 300 baud modem, sells nationally for 59.95, now 39.00!  
Ideal for those with Portuguese Disk Drive system with RS-232 port and software.

Hurry while supplies last as we have made special arrangements with our distributors to make this sale possible.

**English Micro Connection • 15 Kilburn Court • Newport, RI 02840**  
**401/849-3805**

## WEYMIL CORPORATION

...makes a serious commitment to the Timex user in the development of high-quality, innovative, and user-friendly software, complete with layman-oriented documentation, and all at affordable prices. We are proud to offer you:

### \* T H R U S T \*

Finally, real graphics power for your TS 1000! THRUST, the last word in cursor-controlled hi-res graphics for screen or printer output, is a software package composed of SincArtist HR and SincArtist 1.3. Examine this sample for an idea of the powerful versatility of THRUST.

SINCARTIST 1.3 - The original! Fantastic hi-res graphics delivered to the 2040 printer. SincArtist 1.3 boasts excellent user-group reviews and is simply the best non-hardware system available. Note these features:

- 192 X 256 high-resolution file displayed in a 48 X 64 screen window
- Circles, triangles, rectangles, quadrilaterals, rays, inversing, and more
- 40 redefinable patterns and a variety of draw and fill modes
- Cursor or joystick control
- No system modifications required

SINCARTIST HR - The last word in cursor-controlled high-resolution screen graphics. Copy artwork to the 2040 printer and save to tape. SincArtist HR requires a TS 1000 with a socketed 2K RAM, less than \$10.00 in parts, and a few minutes with a soldering iron. Super user-friendly documentation and instructions included. All modifications are fully transparent to other peripherals. HUNTER BOARD OWNERS: All you need is the FREE hardware upgrade that we provide!!!!

THRUST includes SincArtist HR and Sinc-Artist 1.3 (these programs are not sold separately). The Ultimate Hi-Res Tape is available exclusively from Weymil Corporation for only \$20.

### \* M I N I X M O D \*

MINI XMOD - Allows your Westridge or Byte-Back modem to up and download Timex programs to any XModem protocol BBS.

- Fully documented with easy-to-follow instructions for the layman
- 16K and 64K versions included
- Ideal for storage in Hunter Board
- Produced on high-quality cassette for the ZX 81, TS 1000, and TS 1500

MINI XMOD is available from Weymil Corporation for only \$20. Please specify Westridge or Byte-Back version.

WEYMIL CORPORATION  
BOX 5904  
BELLINGHAM WA  
98227-5904

(Write for a free catalogue of other TS 2068 and TS 1000 products)



# Don't Buy a Gorilla Banana!

For several years the "famous" Gorilla Banana dot matrix printer and its clones have been popular with Timex/Sinclair users. The reason was simple — **it was cheap!** Recent magazine ads have even been seen advertising models of this printer for under \$100. But the disadvantages of the Gorilla printer were many: it had poor letter quality using only 5 x 7 dots for forming characters; it provided no true true descenders on letters like y, p, and g; it could not handle single sheets of non-computer paper; it was not particularly compatible with available interfaces and software; and it only offered one basic typeface along with the double-width of that face.

## Introducing the Brother Dot Matrix Printer! for only \$149.95\*!



shown with optional tractor feed

ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDefghi12345  
ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDEF GHI jklmnop1234567890  
ABCDefghi12345  
ABCDefghi123 ABCDefghi123

actual print samples

The **Brother Dot Matrix Printer** is the best value on the market today! It operates on 110-120 volts, weighs but 6½ pounds, and is a very compact 3"x13"x7½" in size to save desk space. It prints at **50 characters per second** (about 35 seconds for a single double spaced page). It is **fully Epson compatible** and uses a **9 x 9** dot matrix pattern for true descenders. It prints on **any type paper** and has **friction feed**. It has **pica, elite, condensed, italics, double-width, sub and superscripts, bold, double-strike, underline**. **Full graphics capabilities** are built-in. It is fully compatible with Tasman, A & J, Rotronics, Aerco, and any other interface that supports Epson printers. It comes standard with **both parallel and serial interfaces** so that it will operate with the new Sinclair QL as well as all other Timex and Sinclair computers with appropriate interfaces.

**\*Price includes shipping (in U.S.A.) and all above listed features. Optional tractor feed—add \$25.00. Florida residents must add 5% sales tax.**

**Foot Software — P.O. Box 14655 — Gainesville, FL 32604  
904/462-1086**

# 3 IN 1

## DELTA DISK INTERFACE

FOR THE

# QL

**Call For  
CURRENT  
PRICES!**

### UNIQUE 3 IN 1 FEATURES

- Double Density Disk Interface
- Centronic Printer Interface
- Memory Expansion

- Support up to 4 Drives
- RAM Disk facility
- Centronic printer interface built in
- Compatible with Microdrive



- Compatible with most QL Software
- Upgradable to 128 K RAM
- Available in two versions:  
DELTA BASIC (no memory)  
DELTA 128 (with 128 K RAM)

### Technology Research Limited

Available from These American Dealers

#### RUSSELL ELECTRONICS

RD 1 Box 539, Centre Hall, PA 16828  
814/364-1325

#### QL CONNECTION

15 Kilburn Court, Newport, RI 02840  
401/849-3805

#### E - Z KEY

Suite 75, 711 S. Artery, Quincy, MA 02169

#### KNIGHTED COMPUTERS

707 Highland Street, Fulton, NY 13069  
315/593-8219

# CTM

The monthly magazine with a natural blending of two popular hobbies — Ham Radio and Computers

U.S.A. .... \$15.00 for 13 issues  
Mexico, Canada ..... \$25.00  
Foreign ..... \$35.00(land) - \$55.00(air)  
(U.S. funds only)  
Permanent (U.S. Subscription) ..... \$100.00  
Sample Copy ..... \$3.50



Circulation Manager  
1704 Sam Drive  
Birmingham, Alabama 35235  
Phone 205/854-0271

## QuarTerS

A quarterly publication for the Timex/Sinclair computer user.

"...Every issue has been full of helpful articles, great software reviews and new product information. Thanks for publishing a needed magazine for TS computer owners and for keeping it easy to read and understand. I have read other TS computer magazines, but none have been as helpful to me as QuarTerS...I'm really glad I subscribed to QuarTerS..."-C. Bower

One year subs. only \$8.00. Overseas only \$11.00(US\$). Check or MO to: WMJ DATA SYSTEMS, 4 Butterfly Dr, Hauppauge, NY 11788.

**FREE FIRST ISSUE**

**SUM**


Send this coupon to WMJ Data Systems, 4 Butterfly Drive, Hauppauge, NY 11788. You will receive one free issue of QIS and we will bill you for a one year subscription. If you do not want to subscribe write cancel on the bill and keep your free issue.

NAME \_\_\_\_\_  
STREET \_\_\_\_\_  
CITY \_\_\_\_\_  
STATE \_\_\_\_\_ ZIP \_\_\_\_\_

# T-S Horizons

Affordable Quality for the Timex Computer User

Each issue brings you 40 pages of usable information, program listings, product reviews, programming articles, hardware projects, and applications for your computer. T-S HORIZONS features nationally known authors like Paul Hunter, Gordon Young, and others. The price is ONLY \$15.00 for a full year (12 issues) AND for a limited time only, new subscribers will receive our special telecommunications issue (#7, see below) \*FREE\* with their subscription.




**T-S Horizons**  
August No. 7 \$125



TS-2068 PROGRAMS  
TIPS  
REVIEWS  
Hardware & Setup

TS-1000/1500  
BANK SWITCHING-4  
"WORM"-CONCLUDED  
POWER SUPPLY?  
New Column

**TIMEX sinclair**



IN T-S HORIZONS #7

\* Byte Back Modem Review  
\* 2068 Programming Tips

IN T-S HORIZONS #7

\* How a Compiler Works \* Telecommunications for Beginner  
\* Book & Game Reviews \* Rotating Globe Routine  
Articles By Gordon Young and Paul Hunter \* Sinclair Info. Net.  
\* TS-1000 Power Supply - and more!!!

CLIP & RETURN TODAY


Enclose \$15 (US) for 12-issue subscription, plus \*FREE\* back issue (while supplies last). \$21 Canada, \$25 other foreign. Extra back issue/sample:\$2.00.

NAME \_\_\_\_\_  
ADDRESS \_\_\_\_\_  
CITY \_\_\_\_\_  
STATE, ZIP \_\_\_\_\_

SEND TO:  
T-S HORIZONS  
2002 Summit Street  
Portsmouth, Ohio 45662

**SUM** \* SATISFACTION GUARANTEED \*

Timex / Sinclair Owners...  
**TAKE A LOOK!**



**TIME DESIGNS  
MAGAZINE**

FOR YOUR  
2068 - 1000/1500 - SPECTRUM

\* Readers nationwide (and Canada too!)  
\* 36 Illustrated Pages  
\* Published "On Time"  
\* Interesting Articles / Programs  
\* Current Information  
\* Exclusive "T/S Shopper" Guide

**ONLY  
\$15 year  
SIX ISSUES**

**SUBSCRIBE TODAY!**

SAVE \$3.00 Off Newstand Price...Send Coupon (or a copy) with Check or Money Order for \$15 (U.S. Funds Only) to address posted below. We will start your subscription right away upon receipt of your order.

TIME DESIGNS MAGAZINE COMPANY  
29722 Hill Rd. • Cotton, Oregon 97017

Name: \_\_\_\_\_  
Address: \_\_\_\_\_  
City / State \_\_\_\_\_ Zip \_\_\_\_\_



# Midwest Timex/Sinclair Computerfest

## May 3-4, 1986 — Cincinnati, OH

The Midwest Timex/Sinclair Computerfest is going to be a reality! Organized and sponsored by users from Ohio, Indiana and Kentucky, this event promises to be an outstanding assembly of T/S users from throughout the Midwest and the nation. It will be held May 3-4 from 9 am to 5 pm at the Ramada Inn in Sharonville and is easily accessible from anywhere in the Cincinnati area.

Individual registrations are \$4 in advance, family registrations are \$7 in advance. Send check or money order to The Midwest T/S Computerfest, 3832 Watterson Ave., Cincinnati, Ohio 45227.

### EXHIBITORS WHO WILL BE THERE!

Knighted Computers  
E. Arthur Brown  
Curry Computers  
Aerco, Inc.  
Time Designs

Budget Computer Services  
Zebra Systems  
SUM Magazine  
TS Horizons  
T/S Connection

Zenith Data Systems  
Cleveland Users Group  
Cincinnati Users Group  
...many others!

**For more information, contact:**  
**Midwest T/S Computerfest, 3832 Watterson Ave., Cincinnati, OH 45227**

### ORDER BLANK

- ☐ I want to subscribe/extend (circle one) my subscription to *SUM Magazine* for one year. Enclosed is:  
☐ \$15.00 (U.S. only) ☐ \$18.00 (Canada & Mexico — U.S. funds)

- ☐ I want to order **The Best of Sum** at \$9.95 postpaid.  
(Contains the best articles from SUM thru 12/85.)

Please do not order from earlier Order Forms as no back issues are currently available.

NAME \_\_\_\_\_

Address \_\_\_\_\_

City/State/Zip \_\_\_\_\_

Expiration Date on label \_\_\_\_\_

Make all checks payable to "SUM Magazine". All prices are postage paid.  
**SUM MAGAZINE — 3224 NW 30 Avenue — Gainesville, Florida 32605**



3224 Northwest 30th Avenue  
Gainesville, Florida 32605

PLEASE EXPEDITE DELIVERY

BULK RATE  
U.S. POSTAGE  
PAID  
PERMIT NO. 460  
Gainesville, FL